# FieldSmart® Fiber Delivery Point (FDP)

## Macro/Small Cell Wall Box -



## **Application**

Engineered to land small to medium fiber terminations in a convenient wall box design, the FieldSmart FDP Macro/Small Cell Wall Box is ideal for a variety of applications, including harsh environment locations surrounding fiber demarcation, entrance facilities, FTTP drop boxes and cell backhaul.

## **Description**

The FieldSmart FDP Macro/Small Cell Wall Box comes with a factory-installed cable assembly, supporting up to 24 fibers. Factory-installed cable reduces the operating costs of fiber deployment by reducing installation times.

### **Features and Benefits**

### Integrity

- RUS listed
- Supports industry standard SC, LC and MPO singlemode connectors
- · Dual snap locks to ensure lid seals to base
- · NEMA 4 rated

#### **Protection**

- · Slack storage clips for both incoming and outgoing fibers
- · Security screw with ability to secure with padlock
- Gasket seal
- · Grounding lug included


#### Access

- · Wall and pole mount
- · Easy to install with both internal and external mounting holes
- Two bottom ¾" (19.05 mm) entry/exit ports are supported with ship-along Sealcon connectors

#### Investment

- Pre-connectorized cable assemblies eliminate labor and speed network construction
- Patch only
- · One box for a variety of application uses





www.SeeClearfield.com 1-800-422-2537

## FieldSmart® Fiber Delivery Point (FDP)





## **Technical Specifications**

FieldSmart FDP Macro/Small Cell Wall Box	
Dimensions	12.17" H x 8.62" W x 3.91" D (309.12 mm x 218.95 mm x 99.31 mm)
Port Density	Up to 24 LC ports
Connector Types	SC/UPC, SC/APC, LC/UPC, LC/APC, MPO
Cable Types	Indoor Riser, Indoor Plenum, Outdoor (Riser/Non-Rated), FieldShield®
Material	UV stabilized, flame retardant polymer (PVC)
Mounting Options	Wall and Pole Mount

## **Configured Part Numbers**

